Uniform Mitigation Verification Inspection Form

Maintain a copy of this form and any documentation provided with the insurance policy

Inspection Date: 06/16/2020				
Owner Information				
Owner Name: Gardens Of St. Andrews		Contact Person:		
Address: 803 Monstrose Dr		Home Phone:		
City: Venice	Zip: 34293	Work Phone:		
County: Sarasota		Cell Phone:		
Insurance Company:		Policy #:		
Year of Home: 1996	# of Stories: 2	Email:		

NOTE: Any documentation used in validating the compliance or existence of each construction or mitigation attribute must accompany this form. At least one photograph must accompany this form to validate each attribute marked in questions 3 though 7. The insurer may ask additional questions regarding the mitigated feature(s) verified on this form.

- 1. **Building Code**: Was the structure built in compliance with the Florida Building Code (FBC 2001 or later) OR for homes located in the HVHZ (Miami-Dade or Broward counties), South Florida Building Code (SFBC-94)?
 - A. Built in compliance with the FBC: Year Built _____. For homes built in 2002/2003 provide a permit application with a date after 3/1/2002: Building Permit Application Date (MM/DD/YYYY) ___/ /____
 - B. For the HVHZ Only: Built in compliance with the SFBC-94: Year Built _____. For homes built in 1994, 1995, and 1996 provide a permit application with a date after 9/1/1994: Building Permit Application Date (MM/DD/YYYY) ___/__/
 - C. Unknown or does not meet the requirements of Answer "A" or "B"
- <u>Roof Covering:</u> Select all roof covering types in use. Provide the permit application date OR FBC/MDC Product Approval number OR Year of Original Installation/Replacement OR indicate that no information was available to verify compliance for each roof covering identified.

2.1 Roof Covering Type:	Permit Application Date	FBC or MDC Product Approval #	Year of Original Installation or Replacement	No Information Provided for Compliance
1. Asphalt/Fiberglass Shingle	//			
☑ 2. Concrete/Clay Tile	01/9 / 2020		2020	
3. Metal	//			
4. Built Up	//			
5. Membrane	//			
6. Other	/			\square

- A. All roof coverings listed above meet the FBC with a FBC or Miami-Dade Product Approval listing current at time of installation OR have a roofing permit application date on or after 3/1/02 OR the roof is original and built in 2004 or later.
- B. All roof coverings have a Miami-Dade Product Approval listing current at time of installation OR (for the HVHZ only) a roofing permit application after 9/1/1994 and before 3/1/2002 OR the roof is original and built in 1997 or later.
- C. One or more roof coverings do not meet the requirements of Answer "A" or "B".
- D. No roof coverings meet the requirements of Answer "A" or "B".

3. Roof Deck Attachment: What is the weakest form of roof deck attachment?

- A. Plywood/Oriented strand board (OSB) roof sheathing attached to the roof truss/rafter (spaced a maximum of 24" inches o.c.) by staples or 6d nails spaced at 6" along the edge and 12" in the field. -OR- Batten decking supporting wood shakes or wood shingles. -OR- Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that has an equivalent mean uplift less than that required for Options B or C below.
- B. Plywood/OSB roof sheathing with a minimum thickness of 7/16"inch attached to the roof truss/rafter (spaced a maximum of 24"inches o.c.) by 8d common nails spaced a maximum of 12" inches in the field.-OR- Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that is shown to have an equivalent or greater resistance than 8d nails spaced a maximum of 12 inches in the field or has a mean uplift resistance of at least 103 psf.
- C. Plywood/OSB roof sheathing with a minimum thickness of 7/16"inch attached to the roof truss/rafter (spaced a maximum of 24"inches o.c.) by 8d common nails spaced a maximum of 6" inches in the field. -OR- Dimensional lumber/Tongue & Groove decking with a minimum of 2 nails per board (or 1 nail per board if each board is equal to or less than 6 inches in width). -OR-

Inspectors Initials $\underline{\mathcal{E}}^{\mathcal{M}}$ Property Address 803 Monstrose Dr, Venice , 34293

*This verification form is valid for up to five (5) years provided no material changes have been made to the structure or inaccuracies found on the form.

OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155

Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that is shown to have an equivalent or greater resistance than 8d common nails spaced a maximum of 6 inches in the field or has a mean uplift resistance of at least 182 psf.

			d Concrete Roof Deck.
		Other:	or unidentified.
H		No attic a	
	eet of	the inside	achment: What is the WEAKEST roof to wall connection? (Do not include attachment of hip/valley jacks within e or outside corner of the roof in determination of WEAKEST type)
	A. 1	oe Nails	
			Truss/rafter anchored to top plate of wall using nails driven at an angle through the truss/rafter and attached to the top plate of the wall, or
			Metal connectors that do not meet the minimal conditions or requirements of B, C, or D
Mi	nimal	conditio	ons to qualify for categories B, C, or D. All visible metal connectors are:
		~	Secured to truss/rafter with a minimum of three (3) nails, and
		~	Attached to the wall top plate of the wall framing, or embedded in the bond beam, with less than a ¹ / ₂ " gap from the blocking or truss/rafter and blocked no more than 1.5" of the truss/rafter, and free of visible severe corrosion.
	B. C	Clips	
			Metal connectors that do not wrap over the top of the truss/rafter, or
			Metal connectors with a minimum of 1 strap that wraps over the top of the truss/rafter and does not meet the nail position requirements of C or D, but is secured with a minimum of 3 nails.
~	C. S	ingle Wr	•
_			Metal connectors consisting of a single strap that wraps over the top of the truss/rafter and is secured with a minimum of 2 nails on the front side and a minimum of 1 nail on the opposing side.
	D. I	Double W	-
			Metal Connectors consisting of 2 separate straps that are attached to the wall frame, or embedded in the bond beam, on either side of the truss/rafter where each strap wraps over the top of the truss/rafter and is secured with a minimum of 2 nails on the front side, and a minimum of 1 nail on the opposing side, or
			Metal connectors consisting of a single strap that wraps over the top of the truss/rafter, is secured to the wall on both sides, and is secured to the top plate with a minimum of three nails on each side.
		tructural ther:	
	G. L	Jnknown	or unidentified
	H. N	No attic a	ccess
			What is the roof shape? (Do not consider roofs of porches or carports that are attached only to the fascia or wall of over unenclosed space in the determination of roof perimeter or roof area for roof geometry classification).
	A. F	lip Roof	Hip roof with no other roof shapes greater than 10% of the total roof system perimeter.
		Tat Roof	Total length of non-hip features: feet; Total roof system perimeter: feet
		Other Roo	less than 2:12. Roof area with slope less than 2:12 sq ft; Total roof area sq ft
6. <u>Se</u>	A. S	SWR (also heathing	r Resistance (SWR): (standard underlayments or hot-mopped felts do not qualify as an SWR) o called Sealed Roof Deck) Self-adhering polymer modified-bitumen roofing underlayment applied directly to the or foam adhesive SWR barrier (not foamed-on insulation) applied as a supplemental means to protect the from water intrusion in the event of roof covering loss.
	B. N	lo SWR.	
	τ. τ	JIKHOWN	or undetermined.
Inspec	ctors I	nitials <u>E</u>	M Property Address 803 Monstrose Dr, Venice , 34293

*This verification form is valid for up to five (5) years provided no material changes have been made to the structure or inaccuracies found on the form. OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155 Page 2 of 4 Opening Protection: What is the <u>weakest</u> form of wind borne debris protection installed on the structure? First, use the table to determine the weakest form of protection for each category of opening. Second, (a) check one answer below (A, B, C, N, or X) based upon the lowest protection level for ALL Glazed openings and (b) check the protection level for all Non-Glazed openings (.1, .2, or .3) as applicable.

Opening Protection Level Chart		Glazed Openings				Non-Glazed Openings	
Place an "X" in each row to identify all forms of protection in use for each opening type. Check only one answer below (A thru X), based on the weakest form of protection (lowest row) for any of the Glazed openings and indicate the weakest form of protection (lowest row) for Non-Glazed openings.		Windows or Entry Doors	Garage Doors	Skylights	Glass Block	Entry Doors	Garage Doors
N/A	Not Applicable- there are no openings of this type on the structure		Х	Х			Х
Α	Verified cyclic pressure & large missile (9-lb for windows doors/4.5 lb for skylights)						
В	Verified cyclic pressure & large missile (4-8 lb for windows doors/2 lb for skylights)						
С	Verified plywood/OSB meeting Table 1609.1.2 of the FBC 2007						
D	Verified Non-Glazed Entry or Garage doors indicating compliance with ASTM E 330, ANSI/DASMA 108, or PA/TAS 202 for wind pressure resistance						
N	Opening Protection products that appear to be A or B but are not verified						
IN	Other protective coverings that cannot be identified as A, B, or C						
х	No Windborne Debris Protection	Х			Х	Х	

<u>A. Exterior Openings Cyclic Pressure and 9-lb Large Missile (4.5 lb for skylights only)</u> All Glazed openings are protected at a minimum, with impact resistant coverings or products listed as wind borne debris protection devices in the product approval system of the State of Florida or Miami-Dade County and meet the requirements of one of the following for "Cyclic Pressure and Large Missile Impact" (Level A in the table above).

- Miami-Dade County PA 201, 202, and 203
- Florida Building Code Testing Application Standard (TAS) 201, 202, and 203
- American Society for Testing and Materials (ASTM) E 1886 and ASTM E 1996
- Southern Standards Technical Document (SSTD) 12
- For Skylights Only: ASTM E 1886 and ASTM E 1996
- For Garage Doors Only: ANSI/DASMA 115
- A.1 All Non-Glazed openings classified as A in the table above, or no Non-Glazed openings exist

A.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level B, C, N, or X in the table above

A.3 One or More Non-Glazed Openings is classified as Level B, C, N, or X in the table above

B. Exterior Opening Protection- Cyclic Pressure and 4 to 8-lb Large Missile (2-4.5 lb for skylights only) All Glazed openings are protected, at a minimum, with impact resistant coverings or products listed as windborne debris protection devices in the product approval system of the State of Florida or Miami-Dade County and meet the requirements of one of the following for "Cyclic Pressure and Large Missile Impact" (Level B in the table above):

- ASTM E 1886 <u>and</u> ASTM E 1996 (Large Missile 4.5 lb.)
- SSTD 12 (Large Missile 4 lb. to 8 lb.)
- For Skylights Only: ASTM E 1886 and ASTM E 1996 (Large Missile 2 to 4.5 lb.)

B.1 All Non-Glazed openings classified as A or B in the table above, or no Non-Glazed openings exist

B.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level C, N, or X in the table above

B.3 One or More Non-Glazed openings is classified as Level C, N, or X in the table above

<u>C. Exterior Opening Protection- Wood Structural Panels meeting FBC 2007</u> All Glazed openings are covered with plywood/OSB meeting the requirements of Table 1609.1.2 of the FBC 2007 (Level C in the table above).

C.1 All Non-Glazed openings classified as A, B, or C in the table above, or no Non-Glazed openings exist

C.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level N or X in the table above

C.3 One or More Non-Glazed openings is classified as Level N or X in the table above

Inspectors Initials EM Property Address 803 Monstrose Dr, Venice, 34293

*This verification form is valid for up to five (5) years provided no material changes have been made to the structure or inaccuracies found on the form.

OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155

N. Exterior Opening Protection (unverified shutter systems with no documentation) All Glazed openings are protected with protective coverings not meeting the requirements of Answer "A", "B", or C" or systems that appear to meet Answer "A" or "B"			
with no documentation of compliance (Level N in the ta	,		
N.1 All Non-Glazed openings classified as Level A, B, C, C			
N.2 One or More Non-Glazed openings classified as Level table above	D in the table above, and no No	n-Glazed openings classified as Level X in the	
N.3 One or More Non-Glazed openings is classified as Lev		and V is the table of an	
X. None or Some Glazed Openings One or more Glaz	ed openings classified and Le	evel X in the table above.	
MITIGATION INSPECTIONS MUST E Section 627.711(2), Florida Statutes, prov	~		
Qualified Inspector Name: Eric Meinheit	License Type: Home Inspector	License or Certificate #: HI1463	
Inspection Company: Inspect2save		Phone: 941-256-0910	
Qualified Inspector – I hold an active license as a	: (check one)		
Home inspector licensed under Section 468.8314, Florida Statut training approved by the Construction Industry Licensing Board	es who has completed the statute and completion of a proficiency		
Building code inspector certified under Section 468.607, Florida			
General, building or residential contractor licensed under Section			
Professional engineer licensed under Section 471.015, Florida S			
Professional architect licensed under Section 481.213, Florida S		na ta proportiv complete a uniform mitigation	
Any other individual or entity recognized by the insurer as possed verification form pursuant to Section 627.711(2), Florida Statute		is to property complete a uniform mitigation	
Individuals other than licensed contractors licensed under			
<u>under Section 471.015, Florida Statues, must inspect the st</u> Licensees under s.471.015 or s.489.111 may authorize a dir			
experience to conduct a mitigation verification inspection.	ect employee who possesses	s the requisite skin, knowledge, and	
Exia Mainhait	and I personally performed	the inspection or (licensed	
(print name)	inu i personany periorineu	the inspection of (<i>ucenseu</i>	
<i>contractors and professional engineers only</i>) I had my employee () perform the inspection (print name of inspector)			
and I agree to be responsible for his/her work.	u i i i i i		
Qualified Inspector Signature: Date: 06/16/2020			
An individual or entity who knowingly or through gross negligence provides a false or fraudulent mitigation verification form is			
subject to investigation by the Florida Division of Insurance			
appropriate licensing agency or to criminal prosecution. (Section 627.711(4)-(7), Florida Statutes) The Qualified Inspector who			
<u>certifies this form shall be directly liable for the misconduct of employees as if the authorized mitigation inspector personally</u> performed the inspection.			
performed the inspection.			
<u>Homeowner to complete</u> : I certify that the named Qualifie residence identified on this form and that proof of identification			
Signature: Date: 06/16/2020			
M. Mrs			
An individual or entity who knowingly provides or utters a false or fraudulent mitigation verification form with the intent to obtain or receive a discount on an insurance premium to which the individual or entity is not entitled commits a misdemeanor of the first degree. (Section 627.711(7), Florida Statutes)			
The definitions on this form are for inspection purposes only and cannot be used to certify any product or construction feature as offering protection from hurricanes.			
Inspectors Initials $\underline{\mathcal{E}^{\mathcal{M}}}$ Property Address 803 Monstrose Dr, Venice , 34293			
*This verification form is valid for up to five (5) years provided no material changes have been made to the structure or inaccuracies found on the form			

inaccuracies found on the form. OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155












8d nails 6x6 Roof Deck Attachment



8d nails 6x6 Roof Deck Attachment



SWR



Single wrap Roof To Wall Attachment



Single wrap Roof To Wall Attachment

803 Monstrose Dr, Venice, 34293