## Uniform Mitigation Verification Inspection Form opy of this form and any documentation provided with the insu

Inspection Date:	of this form and any	documentation prov	vided with the insurance	ce poncy			
Owner Information							
Owner Information Owner Name:			Contact Person:				
Address:				Home Phone:			
City:	Zip:		Work Phone:				
County:	Σip.		Cell Phone:				
Insurance Company:			Policy #:				
Year of Home:	# of Stories:		Email:				
NOTE: Any documentation used in validating the compliance or existence of each construction or mitigation attribute must accompany this form. At least one photograph must accompany this form to validate each attribute marked in questions 3 though 7. The insurer may ask additional questions regarding the mitigated feature(s) verified on this form.							
the HVHZ (Miami-Dade or Browa	1. <u>Building Code</u> : Was the structure built in compliance with the Florida Building Code (FBC 2001 or later) OR for homes located in the HVHZ (Miami-Dade or Broward counties), South Florida Building Code (SFBC-94)?						
☐ A. Built in compliance with the a date after 3/1/2002: Building	Permit Application Date	e (MM/DD/YYYY)/	<u></u>				
☐ B. For the HVHZ Only: Built i provide a permit application w	ith a date after 9/1/1994:	: Building Permit Applic					
☐ C. Unknown or does not meet	the requirements of Ansv	wer "A" or "B"					
2. <b>Roof Covering:</b> Select all roof cov OR Year of Original Installation/R covering identified.							
2.1 Roof Covering Type:	Permit Application Date	FBC or MDC Product Approval #	Year of Original Installation or Replacement	No Information Provided for Compliance			
☐ 1. Asphalt/Fiberglass Shingle	/						
☐ 2. Concrete/Clay Tile							
3. Metal							
4. Built Up	//						
5. Membrane	//						
6. Other	/						
	A. All roof coverings listed above meet the FBC with a FBC or Miami-Dade Product Approval listing current at time of installation OR have a roofing permit application date on or after 3/1/02 OR the roof is original and built in 2004 or later.						
☐ B. All roof coverings have a M roofing permit application afte							
☐ C. One or more roof coverings	•		"B".				
$\Box$ D. No roof coverings meet the	requirements of Answer	"A" or "B".					
3. <b>Roof Deck Attachment</b> : What is t	he weakest form of roof	deck attachment?					
A. Plywood/Oriented strand board (OSB) roof sheathing attached to the roof truss/rafter (spaced a maximum of 24" inches o.c.) by staples or 6d nails spaced at 6" along the edge and 12" in the fieldOR- Batten decking supporting wood shakes or wood shinglesOR- Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that has an equivalent mean uplift less than that required for Options B or C below.							
24"inches o.c.) by 8d common other deck fastening system or	B. Plywood/OSB roof sheathing with a minimum thickness of 7/16"inch attached to the roof truss/rafter (spaced a maximum of 24"inches o.c.) by 8d common nails spaced a maximum of 12" inches in the fieldOR- Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that is shown to have an equivalent or greater resistance than 8d nails spaced a maximum of 12 inches in the field or has a mean uplift resistance of at least 103 psf.						
24"inches o.c.) by 8d common decking with a minimum of 2	C. Plywood/OSB roof sheathing with a minimum thickness of 7/16"inch attached to the roof truss/rafter (spaced a maximum of 24"inches o.c.) by 8d common nails spaced a maximum of 6" inches in the fieldOR- Dimensional lumber/Tongue & Groove decking with a minimum of 2 nails per board (or 1 nail per board if each board is equal to or less than 6 inches in width)OR-Any system of screws, nails, adhesives, other deck fastening system or truss/rafter spacing that is shown to have an equivalent						
Inspectors Initials <u>M</u> Property A	ddress						

\*This verification form is valid for up to five (5) years provided no material changes have been made to the structure. OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155 Page 1 of 4

		or greater resistance than 8d common nails spaced a maximum of 6 inches in the field or has a mean uplift resistance of at leas 182 psf.
		D. Reinforced Concrete Roof Deck.
		E. Other:
		F. Unknown or unidentified.
		G. No attic access.
4.		of to Wall Attachment: What is the <u>WEAKEST</u> roof to wall connection? (Do not include attachment of hip/valley jacks within et of the inside or outside corner of the roof in determination of WEAKEST type)
		A. Toe Nails
		☐ Truss/rafter anchored to top plate of wall using nails driven at an angle through the truss/rafter and attached to the top plate of the wall, or
		☐ Metal connectors that do not meet the minimal conditions or requirements of B, C, or D
	Mi	imal conditions to qualify for categories B, C, or D. All visible metal connectors are:
		☐ Secured to truss/rafter with a minimum of three (3) nails, and
		Attached to the wall top plate of the wall framing, or embedded in the bond beam, with less than a ½" gap from the blocking or truss/rafter <b>and</b> blocked no more than 1.5" of the truss/rafter, <b>and</b> free of visible severe corrosion.
		B. Clips
		☐ Metal connectors that do not wrap over the top of the truss/rafter, <b>or</b>
		☐ Metal connectors with a minimum of 1 strap that wraps over the top of the truss/rafter and does not meet the nat position requirements of C or D, but is secured with a minimum of 3 nails.
		C. Single Wraps  Metal connectors consisting of a single strap that wraps over the top of the truss/rafter and is secured with minimum of 2 nails on the front side and a minimum of 1 nail on the opposing side.
		D. Double Wraps
		Metal Connectors consisting of 2 separate straps that are attached to the wall frame, or embedded in the bond beam, on either side of the truss/rafter where each strap wraps over the top of the truss/rafter and is secured with a minimum of 2 nails on the front side, and a minimum of 1 nail on the opposing side, <b>or</b>
		☐ Metal connectors consisting of a single strap that wraps over the top of the truss/rafter, is secured to the wall on both sides, and is secured to the top plate with a minimum of three nails on each side.
		<ul><li>E. Structural Anchor bolts structurally connected or reinforced concrete roof.</li><li>F. Other:</li></ul>
		G. Unknown or unidentified
		H. No attic access
5.		of Geometry: What is the roof shape? (Do not consider roofs of porches or carports that are attached only to the fascia or wall on host structure over unenclosed space in the determination of roof perimeter or roof area for roof geometry classification).
		A. Hip Roof Hip roof with no other roof shapes greater than 10% of the total roof system perimeter.  Total length of non-hip features: feet; Total roof system perimeter: feet
		B. Flat Roof Roof on a building with 5 or more units where at least 90% of the main roof area has a roof slope of less than 2:12. Roof area with slope less than 2:12 sq ft; Total roof area sq ft
		C. Other Roof Any roof that does not qualify as either (A) or (B) above.
6.	Sec	<ul> <li>A. SWR (also called Sealed Roof Deck) Self-adhering polymer modified-bitumen roofing underlayment applied directly to the sheathing or foam adhesive SWR barrier (not foamed-on insulation) applied as a supplemental means to protect the dwelling from water intrusion in the event of roof covering loss.</li> <li>B. No SWR.</li> <li>C. Unknown or undetermined.</li> </ul>
In	spec	fors Initials Property Address
*T	his '	rerification form is valid for up to five (5) years provided no material changes have been made to the structure or

Page 2 of 4

inaccuracies found on the form.

OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155

7. Opening Protection: What is the weakest form of wind borne debris protection installed on the structure? First, use the table to determine the weakest form of protection for each category of opening. Second, (a) check one answer below (A, B, C, N, or X) based upon the lowest protection level for ALL Glazed openings and (b) check the protection level for all Non-Glazed openings (.1, .2, or .3) as applicable.

Opening Protection Level Chart  Place an "X" in each row to identify all forms of protection in use for each opening type. Check only one answer below (A thru X), based on the weakest form of protection (lowest row) for any of the Glazed openings and indicate the weakest form of protection (lowest row) for Non-Glazed openings.		Glazed Openings				Non-Glazed Openings	
		Windows or Entry Doors	Garage Doors	Skylights	Glass Block	Entry Doors	Garage Doors
N/A	Not Applicable- there are no openings of this type on the structure						
Α	Verified cyclic pressure & large missile (9-lb for windows doors/4.5 lb for skylights)						
В	Verified cyclic pressure & large missile (4-8 lb for windows doors/2 lb for skylights)						
С	Verified plywood/OSB meeting Table 1609.1.2 of the FBC 2007						
D	Verified Non-Glazed Entry or Garage doors indicating compliance with ASTM E 330, ANSI/DASMA 108, or PA/TAS 202 for wind pressure resistance						
N	Opening Protection products that appear to be A or B but are not verified						
IN	Other protective coverings that cannot be identified as A, B, or C						
Х	No Windborne Debris Protection						

A. Exterior Openings Cyclic Pressure and 9-lb Large Missile (4.5 lb for skylights only) All Glazed openings are protected at
a minimum, with impact resistant coverings or products listed as wind borne debris protection devices in the product approval
system of the State of Florida or Miami-Dade County and meet the requirements of one of the following for "Cyclic Pressure
and Large Missile Impact" (Level A in the table above).

- Miami-Dade County PA 201, 202, and 203
- Florida Building Code Testing Application Standard (TAS) 201, 202, and 203

☐ A.1 All Non-Glazed openings classified as A in the table above, or no Non-Glazed openings exist

- American Society for Testing and Materials (ASTM) E 1886 and ASTM E 1996
- Southern Standards Technical Document (SSTD) 12
- For Skylights Only: ASTM E 1886 and ASTM E 1996
- For Garage Doors Only: ANSI/DASMA 115

	☐ A.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level B, C, N, or X in the table above		
	☐ A.3 One or More Non-Glazed Openings is classified as Level B, C, N, or X in the table above		
B. Exterior Opening Protection- Cyclic Pressure and 4 to 8-lb Large Missile (2-4.5 lb for skylights only) All Glopenings are protected, at a minimum, with impact resistant coverings or products listed as windborne debris protection definithe product approval system of the State of Florida or Miami-Dade County and meet the requirements of one of the following for "Cyclic Pressure and Large Missile Impact" (Level B in the table above):			
	• ASTM E 1886 and ASTM E 1996 (Large Missile – 4.5 lb.)		
	• SSTD 12 (Large Missile – 4 lb. to 8 lb.)		
	• For Skylights Only: ASTM E 1886 and ASTM E 1996 (Large Missile - 2 to 4.5 lb.)		
	☐ B.1 All Non-Glazed openings classified as A or B in the table above, or no Non-Glazed openings exist		
	$\square$ B.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level C, N, or X in the table above		
	$\square$ B.3 One or More Non-Glazed openings is classified as Level C, N, or X in the table above		

☐ C. Exterior Opening Protection- Wood Structural Panels meeting FBC 2007 All Glazed openings are covered with

C.2 One or More Non-Glazed openings classified as Level D in the table above, and no Non-Glazed openings classified as Level N or X in

plywood/OSB meeting the requirements of Table 1609.1.2 of the FBC 2007 (Level C in the table above).

C.1 All Non-Glazed openings classified as A, B, or C in the table above, or no Non-Glazed openings exist

 $\square$  C.3 One or More Non-Glazed openings is classified as Level N or X in the table above

Inspectors Initials Property Address

the table above

inaccuracies found on the form.


<sup>\*</sup>This verification form is valid for up to five (5) years provided no material changes have been made to the structure or

N. Exterior Opening Protection (unverified shutter syste protective coverings not meeting the requirements of Answer	ms with no documentation "A", "B", or C" or system	n) All Glazed openings are protected with ms that appear to meet Answer "A" or "B"
with no documentation of compliance (Level N in the table		
N.1 All Non-Glazed openings classified as Level A, B, C, or N i	n the table above, or no Non-I	Glazed openings exist
N.2 One or More Non-Glazed openings classified as Level D in table above		Glazed openings classified as Level X in the
N.3 One or More Non-Glazed openings is classified as Level X	n the table above	
X. None or Some Glazed Openings One or more Glazed op	penings classified and Leve	el X in the table above.
MITIGATION INSPECTIONS MUST BE C Section 627.711(2), Florida Statutes, provides		
Qualified Inspector Name: Steven Rosenbaum Lice	Engineering	License or Certificate #: 49307
Insight Inspections	Ph	(941) 224-9030
Qualified Inspector – I hold an active license as a: (c	neck one)	
<ul> <li>☐ Home inspector licensed under Section 468.8314, Florida Statutes where training approved by the Construction Industry Licensing Board and a Building code inspector certified under Section 468.607, Florida Status General, building or residential contractor licensed under Section 489</li> <li>X Professional engineer licensed under Section 471.015, Florida Statute</li> </ul>	completion of a proficiency ex utes. .111, Florida Statutes.	
Professional architect licensed under Section 481.213, Florida Statute	S.	
Any other individual or entity recognized by the insurer as possessing verification form pursuant to Section 627.711(2), Florida Statutes.	the necessary qualifications t	o properly complete a uniform mitigation
Individuals other than licensed contractors licensed under Sectunder Section 471.015, Florida Statues, must inspect the structure Licensees under s.471.015 or s.489.111 may authorize a direct experience to conduct a mitigation verification inspection.  I, Steven Rosenbaum am a qualified inspector and I (print name)  contractors and professional engineers only) I had my employee and I agree to be responsible for his/her work.  Qualified Inspector Signature:  An individual or entity who knowingly or through gross negliges subject to investigation by the Florida Division of Insurance Frappropriate licensing agency or to criminal prosecution. (Section certifies this form shall be directly liable for the misconduct of performed the inspection.  Homeowner to complete: I certify that the named Qualified Instruction was a complete in this form and that proof of identification was a complete in this form and that proof of identification was a complete in this form and that proof of identification was a complete in the proof of identification was a complete in this form and that proof of identification was a complete in this form and that proof of identification was a complete in the proof of identification w	personally and not the mployee who possesses the personally performed to personally personally and personally personally and not the personally and personally performed the personal personal personally	rough employees or other persons.  The requisite skill, knowledge, and  The inspection or (licensed)  The perform the inspection inspector)  The performance of the statutes and the statutes of the statutes
Signature: Janes Juffy Date	: 2/6/18	
An individual or entity who knowingly provides or utters a falsobtain or receive a discount on an insurance premium to which of the first degree. (Section 627.711(7), Florida Statutes)		
The definitions on this form are for inspection purposes only an as offering protection from hurricanes.	d cannot be used to certi	fy any product or construction feature
Inspectors Initials Property Address 600 Miral	oella Cir.	
*This verification form is valid for up to five (5) years provided inaccuracies found on the form.  OIR-B1-1802 (Rev. 01/12) Adopted by Rule 69O-170.0155	no material changes hav	e been made to the structure or  Page 4 of 4





Gable roof shape, 56 In ft total
Balance of roof is Hip
Gable % = Gable In ft / Total In ft
= 56 / 416 = 13%



8d nails verified



Nail location verified



6" spacing in the field





Single wrap with at least 2 nails on the embedded side and at least 1 nail on the wrapped side